

APPROVED BY THE HIGHLANDS COUNCIL

**Township of Montville Highlands
Preservation Area
Master Plan Element**

Prepared by the State of New Jersey Highlands Water Protection and Planning
Council in Support of the Highlands Regional Master Plan

April 2013

Adopted: _____

HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT

MASTER PLAN SUPPLEMENT
TOWNSHIP OF MONTVILLE
MORRIS COUNTY, NEW JERSEY

MEMBERS OF THE MONTVILLE PLANNING BOARD

Gary Lewis, Chairman
John Visco, Vice Chairman & HPRC Liaison
Ladis Karkowsky
Lawrence Kornreich, Ph.D., Environmental Commission Liaison
Larry Hines
Arthur Maggio
Adam Adrignolo
Tim Braden, Mayor
Don Kostka, Deputy Mayor
Lawrence Tobias, Alternate #1
Angela Morello-Lange, Alternate #2

The Planning Board presented, discussed, and accepted public comment on this Master Plan supplement at its duly-noticed public meeting of August 8, 2013. Copies of the document were made available for review by the public at least 10 days prior to that meeting, and adequate notice of the meeting advising that the Highlands Element was on the agenda for discussion and public comment, was provided.

This document is based on a model Highlands Element prepared and provided to Highlands municipalities by the New Jersey Highlands Water Protection and Planning Council. Modifications required to tailor it for application to the Township of Montville were provided by the individual indicated below.

PREPARED BY:


Joseph H. Burgis, PP, AICP

Professional License No. 2450

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

TABLE OF CONTENTS

| | |
|--|----|
| INTRODUCTION | 1 |
| POLICIES, GOALS & OBJECTIVES..... | 3 |
| A. PRESERVATION AREA GOALS..... | 3 |
| B. GENERAL PURPOSES OF ZONING..... | 4 |
| C. RELATIONSHIP BETWEEN HIGHLANDS ACT & MLUL | 5 |
| LAND USE PLAN | 7 |
| A. HIGHLANDS ZONES AND SUB-ZONES | 7 |
| B. LAND USES | 8 |
| C. DENSITY AND INTENSITY OF DEVELOPMENT..... | 9 |
| D. LAND USE INVENTORY | 11 |
| E. REDEVELOPMENT PLANNING..... | 11 |
| HOUSING PLAN..... | 15 |
| CONSERVATION PLAN | 16 |
| A. FOREST RESOURCES..... | 16 |
| B. HIGHLANDS OPEN WATERS AND RIPARIAN AREAS..... | 17 |
| C. STEEP SLOPES..... | 18 |
| D. CRITICAL HABITAT..... | 19 |
| E. LAKE MANAGEMENT | 21 |
| F. WATER RESOURCES AVAILABILITY | 22 |
| G. PRIME GROUND WATER RECHARGE AREAS | 25 |
| H. WATER QUALITY | 26 |
| I. WELLHEAD PROTECTION | 27 |
| J. LOW IMPACT DEVELOPMENT | 28 |
| UTILITY SERVICES PLAN..... | 31 |
| CIRCULATION PLAN | 33 |
| LAND PRESERVATION AND LAND STEWARDSHIP PLAN..... | 36 |
| COMMUNITY FACILITIES PLAN..... | 39 |
| SUSTAINABLE ECONOMIC DEVELOPMENT PLAN | 40 |
| HISTORIC PRESERVATION PLAN | 41 |

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

| | |
|---|----|
| A. HISTORIC, CULTURAL, AND ARCHAEOLOGICAL RESOURCES..... | 41 |
| B. SCENIC RESOURCES | 43 |
| RELATIONSHIP OF MASTER PLAN TO STATE/REGIONAL/LOCAL PLANS | 44 |
| ACRONYMS | 46 |
| EXHIBITS | 47 |
| APPENDIX A MAJOR POTENTIAL CONTAMINANT SOURCES | 48 |
| APPENDIX B MINOR POTENTIAL CONTAMINANT SOURCES | 49 |

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

INTRODUCTION

The Township of Montville is located in the New Jersey Highlands Region. It is one of 88 municipalities protected by and subject to the provisions of the Highlands Water Protection and Planning Act (“Highlands Act,” N.J.S.A. 13:20-1 et seq.). The Highlands Act was enacted by the State Legislature on August 10, 2004 for the purpose of protecting, enhancing, and restoring Highlands natural resources, in particular water resources, which provide drinking water to over 5 million New Jersey residents. The Highlands Act created the Highlands Water Protection and Planning Council (the “Highlands Council”) and charged it with crafting a comprehensive master plan for the Highlands Region.

To complete that task, the Highlands Council engaged in a four-year planning process involving extensive scientific and technical analysis of the Region, along with an intensive program of public outreach and participation. The Highlands Council solicited the advice and input of all stakeholders and interested parties through a variety of means, including but not limited to: initiation of the “Partnership Program” for municipal and county government representatives; formation of 18 Technical Advisory Committees comprised of technical experts and practitioners in relevant fields such as land use planning, engineering, agriculture, real estate appraisal, transportation, and business; and development of the “Network,” a forum for information-sharing and outreach to the general public. In addition, the Highlands Council has held and continues to adhere to a regular schedule of open public meetings providing continuous opportunity for public comment, and has provided for on-going data sharing and access to information through its internet website.

The Highlands Regional Master Plan (RMP) was adopted by the Highlands Council on July 17, 2008, and became effective on September 8, 2008. As the product of a long-term, participatory, and region-wide planning effort, the RMP is representative of the collective response of the wider community to the Legislature’s call for a Highlands comprehensive master plan. The Township places value in the regional planning process that was undertaken to fully develop the RMP and acknowledges its role in furthering the vision that it represents.

The Highlands Region encompasses some 1,343 square miles in the northwest part of New Jersey. The Highlands Act designates about half of the seven-county Region as Preservation Area (415,000 acres) and the other half as Planning Area (444,000 acres). The Act requires that jurisdictions having lands in the Preservation Area conform to the Highlands RMP with respect to that area, while for lands located in the Planning Area, conformance is voluntary.

The Township of Montville is located partially in each the Preservation and Planning Area. The municipality affirmatively seeks to align its land use planning program with the provisions of the RMP with respect to that portion of the municipality located within the Preservation Area. For purposes of this document, these lands shall be formally designated the “Township Highlands Preservation Area,” with shortened references to the “Highlands Preservation Area,” having the same meaning. This supplement to the Township Master Plan, designated the “Highlands Element,” represents a first step toward achieving full conformance with the Highlands RMP.

TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT

The Highlands Element sets forth the policies that shall guide the future land use and development of the Township Highlands Preservation Area. It provides the rationale and the framework for the adoption of land use regulations that are protective of Highlands resources and consistent with the Highlands RMP. With regard to specific regulatory requirements, these shall apply to non-exempt land use activities in the Highlands Preservation Area. "Non-exempt" land use and development refers to uses, activities, and development projects not expressly listed as exemptions in the Highlands Act (N.J.S.A. 13:20-28). Highlands Act exemptions pertain to specific "activities, improvements and development projects." With the exception of the lands of federal military installations existing at the time of enactment of the Highlands Act, the exemptions do not apply across-the-board to lots, tracts, or any other divisions of land, whether existing or proposed at the time of passage of the Act. Land use activities, improvements, and development projects that are exempt from the Highlands Act shall remain subject to all other applicable provisions of the underlying municipal Master Plan, Zoning and Land Use Ordinances, and Development Regulations.

The Highlands Element amends or creates in limited form (where not already existing), each of the components of the municipal Master Plan, as provided in the sections that follow. The Highlands Element is intended to apply in conjunction with the language of the existing Township Master Plan to the maximum extent feasible. In the event of conflicts between the two, the Highlands Element shall supersede, unless the existing municipal Master Plan provisions are more restrictive.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

POLICIES, GOALS & OBJECTIVES

The Township Highlands Preservation Area is located in the northernmost portion of the municipality. It consists of approximately 3,440 acres of land, occupying approximately 28 percent of the Township (see Exhibit A, Township Highlands Preservation Area).

The Township Highlands Environmental Resource Inventory (ERI) (prepared by Burgis Associates, Inc., and dated August 2012) provides detailed information concerning the physical features, natural resources and specific characteristics of the municipal Highlands Preservation Area. The ERI includes all of the information available through the Highlands Regional Master Plan and supporting technical documents, which document the wide array of natural and cultural resources that characterize the New Jersey Highlands Region.

The municipality recognizes the unique value of the Township Highlands Preservation Area and seeks to protect and enhance it, in keeping with the Highlands Act and the Highlands RMP. Accordingly, the overarching land use policy with respect to the Township Highlands Preservation Area is to place priority emphasis on the protection, enhancement and restoration of Highlands natural and cultural resources while ensuring that land use and development activities therein occur only in a manner and location that is consistent with the Highlands RMP.

In keeping with this policy, the following goals of the Highlands Act and Highlands RMP are embraced by the municipality and shall guide the land use and development of the Township Highlands Preservation Area:

A. PRESERVATION AREA GOALS

1. To protect, restore, and enhance the quality and quantity of surface and ground waters;
2. To preserve extensive and, to the maximum extent possible, contiguous areas of land in its natural state, thereby ensuring retention of the unique and significant natural, scenic, and other resources representative of the Township Highlands Preservation Area;
3. To protect the natural, scenic, and other resources of the Township Highlands Preservation Area, including but not limited to contiguous forests, wetlands, vegetated stream corridors, steep slopes, and critical habitat for fauna and flora;
4. To preserve farmland, historic sites, and other historic resources;
5. To preserve outdoor recreation opportunities on publicly owned land;
6. To promote conservation of water resources;
7. To promote Brownfield remediation and redevelopment, where applicable;

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

8. To promote compatible agricultural, horticultural, recreational, and cultural uses and opportunities within the framework of protecting the environment of the Township Highlands Preservation Area; and
9. To prohibit or limit to the maximum extent possible construction or development which is incompatible with preservation of this unique area.

B. GENERAL PURPOSES OF ZONING

The afore-listed goals for the use and development of lands located within the Township Highlands Preservation Area are consistent with and intended to apply equally and in conjunction with the purposes of zoning as expressed by the New Jersey Municipal Land Use Law (MLUL) (N.J.S.A. 40:55D-1 et seq.). Nothing in the body of the Highlands Element shall be construed to imply that the provisions of the MLUL are not also applicable to the Township in exercising its authority to engage in land use planning and regulation pertinent to the Highlands Preservation Area.

The intents and purposes of the MLUL (N.J.S.A. 40:55D-2) are expressly incorporated herein for application to Township land use planning and management of the Highlands Preservation Area, as follows:

- a. To guide the appropriate use or development of all lands under Township jurisdiction, in a manner which will promote the public health, safety, morals, and general welfare;
- b. To secure safety from fire, flood, panic and other natural and man-made disasters;
- c. To provide adequate light, air and open space;
- d. To ensure that the development of the Township does not conflict with the development and general welfare of neighboring municipalities, the county, or the state as a whole;
- e. To promote the establishment of appropriate population densities and concentrations that will contribute to the well-being of persons, neighborhoods, communities and regions and preservation of the environment;
- f. To encourage the appropriate and efficient expenditure of public funds by the coordination of public development with land use policies;
- g. To provide sufficient space in appropriate locations for a variety of agricultural, residential, recreational, commercial and industrial uses and open space, both public and private, according to their respective environmental requirements in order to meet the needs of all citizens;

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

- h. To encourage the location and design of transportation routes which will promote the free flow of traffic while discouraging location of such facilities and routes which result in congestion or blight;
- i. To promote a desirable visual environment through creative development techniques and good civic design and arrangement;
- j. To promote the conservation of historic sites and districts, open space, energy resources and valuable natural resources in the Township and to prevent urban sprawl and degradation of the environment through improper use of land;
- k. To encourage planned unit developments, where appropriate, which incorporate the best features of design and relate the type, design and layout of residential, commercial, industrial and/or recreational development to the particular site;
- l. To ensure sufficient availability of senior citizen community housing;
- m. To encourage coordination of the various public and private procedures and activities shaping land development with a view of lessening the cost of such development and to the more efficient use of land;
- n. To promote utilization of renewable energy resources; and
- o. To promote the maximum practicable recovery and recycling of recyclable materials from municipal solid waste through the use of planning practices designed to incorporate the State Recycling Plan goals and to complement municipal recycling programs.

C. RELATIONSHIP BETWEEN HIGHLANDS ACT & MLUL

The Municipal Land Use Law gives authority to New Jersey municipalities to govern land use and development within their borders. The Highlands Act augments that authority to allow municipalities the power to enforce the goals, policies, objectives, and programs of the Highlands Regional Master Plan. The Highlands Act and the RMP together provide the regional perspective from which local decisions and actions will emanate.

As a result of the passage of the Highlands Act, the future of land use planning has significantly changed for both municipalities and counties in the Highlands Region. The New Jersey Supreme Court, in upholding the constitutionality of the Highlands Act in OFF, LLC v. State, 197 N.J. 418 (2008), affirmed the Appellate Division's decision, which emphasized the broad scope of the Highlands Act to protect the natural and agricultural resources of the Highlands through a coordinated system of regional land use controls. The Highlands Act creates a system in which a regional plan is designed to be implemented primarily through local government units. The net effect is that the statutory authority of local government units in the Highlands Region, inclusive of that provided under the Municipal Land Use Law (MLUL), is not preempted by the Highlands Act, but rather is

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

supplemented through the passage of the Highlands Act and the adoption of the Highlands Regional Master Plan. The Highlands Act provides, through the conformance of municipal master plans and ordinances with the Highlands RMP, authorities for municipal regulation that are in addition to those of the MLUL.

Accordingly, the criteria for approval of development applications under the ordinances that ultimately effectuate this Highlands Element will incorporate aspects of both the Municipal Land Use Law and the Highlands Act. To the extent that MLUL criteria for approval of variances, waivers, exceptions and/or any other relevant aspect are altered or supplemented by provisions indicated in the Highlands Element, authority for such modifications derives from passage of the Highlands Act.

The Highlands Council will coordinate with NJDEP during Highlands permit review for any major Highlands development including the review of waivers on a case-by-case basis: 1) if determined to be necessary in order to protect public health and safety; 2) for redevelopment in accordance with a Highlands Redevelopment Area Designation (see Land Use Plan, Section F); or 3) in order to avoid the taking of property without just compensation.

LAND USE PLAN

A. HIGHLANDS ZONES AND SUB-ZONES

The Township Highlands Preservation Area includes the Highlands Zones and Sub-Zones listed and described below. These Zones are configured as depicted in Exhibit A (“Township Highlands Preservation Area”) and are herewith incorporated into the Land Use Plan as an overlay to the existing Land Use Plan. The Highlands Council delineation of Highlands Zones finds basis in the underlying natural resources, the extent of existing development and supporting infrastructure, and the potential to support new development and/or redevelopment. Highlands Zones are intended to ensure that the density and intensity of future development and/or redevelopment do not exceed the capacity of the land, natural resources, and existing infrastructure to support it.

The Highlands Zones include three primary zones (the Protection Zone, Conservation Zone, and Existing Community Zone) and four sub-zones (Wildlife Management Sub-Zone, Conservation Zone–Environmentally Constrained Sub-Zone, Existing Community Zone–Environmentally Constrained Sub-Zone, and Lake Community Sub-Zone) each with its own purpose, application and development criteria. The zones and sub-zones included in the Township Highlands Preservation Area are as follows:

1. **Protection Zone.** The Protection Zone consists of the highest quality natural resource value lands that are essential to maintaining water quality, water quantity and sensitive ecological resources and processes. Land acquisition is a high priority for lands in the Protection Zone and development activities will be extremely limited. Any development will be subject to stringent limitations on consumptive and depletive water use, degradation of water quality, and impacts to environmentally sensitive lands and natural resources.
2. **Existing Community Zone.** The Existing Community Zone consists of areas of concentrated development representing existing communities. These areas tend to have limited environmental constraints due to previous development patterns, and may have existing infrastructure that can support additional development and/or redevelopment. Where served by adequate supporting infrastructure, lands within the Existing Community Zone are suited to higher densities and intensities of development (see Section C, below) than other Zones. This Zone has the greatest potential to accommodate mixed-use development projects and center-based planning initiatives, generally.
 - a. **Existing Community Zone–Environmentally Constrained Sub-Zone.** The Existing Community Zone–Environmentally Constrained Sub-Zone consists of significant contiguous critical habitat, steep slopes and forested lands within the Existing Community Zone that should be protected from further fragmentation. They serve as regional habitat “stepping stones” to larger contiguous critical habitat and forested areas. As such, they are not appropriate for significant development, and are best served by land preservation and protection.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

Development is subject to stringent limitations on consumptive and depletive water use, degradation of water quality, and impacts to environmentally sensitive lands.

- b. **Lake Community Sub-Zone.** The Lake Community Sub-Zone consists of patterns of community development that are within the Existing Community Zone within 1,000 feet of lakes. Lakes are defined to include those 10 acres or greater in size with lake management areas consisting of lands within the first 1,000 feet (or less, depending on the protection focus) from the lake shoreline. The purpose for the sub-zone is to protect and enhance water quality, resource features, shoreline recreation, scenic quality, and community character. This zone incorporates unique regulatory requirements to prevent degradation of water quality, harm to lake ecosystems, and watershed pollution, while promoting natural aesthetic values within the Existing Community Zone.

In light of the significant environmental constraints that affect many of the Highlands Zones and Sub-Zones, future growth should be channeled into compact centers within them, where feasible, provided suitable locations can be identified. Such development must incorporate smart growth principles and should be designed at densities (see Section C, below) appropriate to the Zone, the community character, and the capacities of the water and wastewater systems (including septic systems) that support them. The Planning Board will examine the potential for such opportunities.

B. LAND USES

The intents and purposes for each municipal land use category or zoning district, as set forth by the underlying Land Use Plan, are herewith amended to recognize and give priority to the intents and purposes listed above for the Highlands Zones and Sub-Zones. As to land use classifications (e.g., single- or multi-family residential, commercial, industrial) and specific permitted land uses, a thorough review and comparison between municipal and Highlands Zones and Sub-Zones must be undertaken to assess compatibility and to determine whether zoning amendments (pertinent to non-exempt development) are necessary to achieve consistency. Until such time as that examination is complete, permitted uses shall remain in effect for non-exempt development, with the significant caveat that each is subject to compliance with: a) all resource constraints (discussed at length in the Conservation Plan Element); b) all applicable provisions of both the NJDEP Highlands Water Protection and Planning Act Rules (N.J.A.C. 7:38) and the New Jersey Department of Agriculture (NJDA) Agricultural Development in the Highlands Rules (N.J.A.C. 2:92); and c) the density and intensity requirements set forth in the section that follows (see Section C, Density and Intensity of Development).

Specific immediate changes to permitted uses will include the following, each pending the adoption of implementing ordinance provisions approved by the Highlands Council:

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

1. ***Prime Ground Water Recharge Area.*** Upon adoption of the appropriate regulatory provisions, any principal and/or accessory use or structure related or devoted to a use which has a significant potential for discharge of hazardous materials, where otherwise permitted by the municipal ordinance, shall be prohibited from any portion of the Highlands Preservation Area delineated as a “Prime Ground Water Recharge Area” (as defined and delineated in the Conservation Plan Element).
2. ***Wellhead Protection Area (Tier 1 and 2).*** Upon adoption of the appropriate regulatory provisions, any principal and/or accessory use or structure related or devoted to such use, which has a significant potential for discharge of hazardous materials, where otherwise permitted by the municipal ordinance, shall be expressly prohibited from any portion of the Highlands Preservation Area delineated as a Tier 1 or Tier 2 “Wellhead Protection Area” (as defined and delineated in the Conservation Plan Element).
3. ***Wellhead Protection Area (Tier 1).*** Upon adoption of the appropriate regulatory provisions, any principal and/or accessory use or structure related or devoted to such use, which is designated as a Major or Minor Potential Contaminant Source (PCS) by the Highlands Council (see Appendices A and B) where otherwise permitted by the municipal ordinance, shall be prohibited from that portion of any Tier 1 Wellhead Protection Area lying within 200 feet of the wellhead (Tier 1 Wellhead Protection Area (as defined and delineated in the Conservation Plan Element)).

C. DENSITY AND INTENSITY OF DEVELOPMENT

The physical potential for development and/or redevelopment in each Highlands Zone and Sub-Zone of the Township Highlands Preservation Area is limited by existing natural features, resource protection priorities, and the capacity of the land and available infrastructure to support it. This section sets forth a capacity-based planning framework intended to ensure that future development and redevelopment do not exceed carrying capacity.

To the extent that the existing development density and intensity standards of the underlying zone districts (as defined and applied under the existing Land Use Plan and Zoning Ordinance) are consistent with the parameters of this section, they shall remain in effect. Where any density or intensity goals of the existing Land Use Plan are inconsistent with these limits, they are herewith modified with respect to the Highlands Preservation Area, to the extent necessary to conform to the Highlands RMP. For purposes of these provisions, density of development standards refer to the requirements of the underlying Zoning Ordinance that regulate the permitted number of dwelling units per acre of land, whether specifically defined as density standards or set forth as minimum lot size requirements for application to specific zoning districts. Intensity of development standards refer to those requirements used to define the relationship between the permitted extent,

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

form and location of development of a lot, to the size, shape, and configuration of the lot on which it is situated (e.g., floor area ratio, building coverage, building height, yard setbacks, number of stories).

In the context herein, modifications to the underlying density or intensity of development standards will occur only to the extent that existing standards conflict with provisions of the Highlands Act, NJDEP Preservation Area Rules, or RMP, in particular those concerning water availability or available septic system yield. These modifications shall not apply to lawfully existing or approved development in the Highlands Preservation Area at the time of adoption of the ordinances that effectuate such provisions. They shall apply, however, if modifications or improvements to such existing development result in an increase in demand for water availability or septic system yield (excluding any increase directly attributed to exercise of a Highlands Act exemption).

Permitted densities and intensities of development shall comport with the provisions of the Highlands RMP, Highlands Council Technical Reports and all data related thereto, and the applicable provisions of the Preservation Area Rules adopted by the NJDEP (N.J.A.C. 7:38). As provided therein, the framework for setting development density/intensity guidelines relies primarily on water and wastewater capacity analyses, with natural resource constraints to be applied largely on a project-specific basis at the development review level.

Permitted density and intensity allowances for the Highlands Preservation Area must also reflect municipal intents with respect to growth and development of the community. A comprehensive analysis will be required as follow-up to adoption of the Highlands Element, to determine specific density and intensity allowances for future non-exempt development within the Highlands Preservation Area. The Board will, with the assistance of its professionals, complete this analysis to determine: 1) the capacity for future growth and development of the Highlands Preservation Area (based on the RMP, Technical Reports, NJDEP Rules); 2) the extent to which such growth may be appropriate within the relevant portions of the community; and 3) the specific allocation of such growth and development over the Highlands Zones and Sub-Zones. (This analysis will take place with assistance from the Highlands Council after the Township has achieved Basic Plan Conformance.)

Until such time as the full analysis can be completed, applications for development within the Highlands Preservation Area require reviews for consistency on a project-by-project basis. The major criteria for assessing the proposed density/intensity of development include the following:

1. **Base Maps/Data.** Base data regarding water availability and wastewater treatment capacity appear in the technical information provided in the Conservation Plan and Utility Services Plan Elements, which includes associated mapping identified as Exhibits P, T, and U. These include, respectively, maps of the Township Highlands Preservation Area: Net Water Availability, Public Community Water Systems, and Highlands Domestic Sewerage Facilities. All are herewith adopted and incorporated as a component of the Highlands Element.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

2. **Water Availability.** As provided under Conservation Plan Element Section F, Water Resources Availability.
3. **Public Water Supply and Wastewater Utilities.** Where properties are served by existing water and wastewater utility infrastructure having sufficient available capacity, the density and intensity of new development shall be consistent with the requirements of existing zoning.
4. **Public Water Supply Utilities – Key Provisions.** New, expanded, or extended public water systems are prohibited unless approved through issuance of either a Highlands Applicability Determination indicating that a project is exempt from the Highlands Act, or a Highlands Preservation Area Approval with waiver pursuant to N.J.A.C. 7:38.
5. **Wastewater Utilities – Key Provisions.** New, expanded or extended wastewater collection and treatment systems and community on-site treatment facilities are prohibited unless approved through issuance of either a Highlands Applicability Determination indicating that a project is exempt from the Highlands Act, or a Highlands Preservation Area Approval with waiver pursuant to N.J.A.C. 7:38.
 - i. **Septic Systems – Key Provisions** Any Major Highlands Development (as defined at N.J.A.C. 7:38) involving the installation of one or more new individual subsurface disposal systems (or aggregate of equivalent disposal units as provided) shall meet NJDEP septic system density requirements as set forth at N.J.A.C. 7:38.

D. LAND USE INVENTORY

Planning for the future of the Highlands Preservation Area requires a clear understanding and assessment of existing land uses and development within the Area, in the areas surrounding it, and throughout the municipality. The Township Land Use Inventory, prepared by Burgis Associates, Inc. in August 2012 (see Exhibit B), is representative of the Township’s most current knowledge of land use and development conditions within the municipality.

E. REDEVELOPMENT PLANNING

The Planning Board will examine the potential for redevelopment opportunities within the Highlands Preservation Area. The term “redevelopment” is used herein to refer to reconstruction or re-use of previously developed and underutilized properties (which include Preservation Area sites having 70% or more area in impervious surface), and to the rehabilitation and re-use of “brownfield” sites (identified as such by NJDEP). Unless specifically stated otherwise, neither the term “redevelopment,” nor the phrase “in need of redevelopment” is used herein to invoke the definitions, processes, powers or any other

TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT

facet of the provisions of the New Jersey Local Redevelopment and Housing Law (N.J.S.A. 40A:12A-1 et seq.).

Rather, Highlands Preservation Area redevelopment planning refers to the identification of previously developed areas that: a) are suitable for re-use and/or reconstruction, or reversion to “greenfields,” such as parklands, conservation areas, or open space; and/or b) may be eligible for designation by the Highlands Council as Highlands Redevelopment Areas. Highlands Redevelopment Areas are typically characterized by ready access to or potential for water and wastewater utility infrastructure (and available or potential capacities); existing transportation infrastructure and/or services with links to viable transportation networks; proximity to supporting community facilities and services; and suitability for increased development intensity in keeping with smart growth planning principles. Where brownfields are involved, NJDEP identification of the brownfield site is a necessary step prior to Highlands Council designation of a Highlands Redevelopment Area. Such applications must be submitted to NJDEP for a Highlands Preservation Area Approval (HPAA) with Redevelopment Waiver.

It is the intent of this Plan to encourage redevelopment where appropriate within the Highlands Preservation Area, to ensure optimal and efficient use of land. By maximizing the use of previously developed areas and areas in need of environmental clean-up or other improvements, the municipality may provide for desirable new development (or new green spaces), while protecting lands that contain sensitive environmental features and important Highlands resources. This approach is intended to guide development toward the most suitable locations in the municipality, to encourage environmental clean-up where needed, and to maximize the use of existing infrastructure to meet future needs.

Redevelopment projects and activities that conform to density/intensity allowances and meet all other requirements of the applicable land use ordinances (specifically including those developed for the Highlands Preservation Area and the Highlands Preservation Area Rules at N.J.A.C. 7:38), do not require Highlands Redevelopment Area designation and may proceed as of right in accordance with all municipal procedural requirements. Any municipally-sponsored redevelopment project proposed pursuant to N.J.S.A. 40A:12A, while perhaps also requiring Highlands Council Redevelopment Area designation, must be advanced in accordance with all applicable statutory requirements, including preparation and adoption by the Governing Body of a Redevelopment Plan. The Planning Board, in making any Highlands Preservation Area determination of “area in need of redevelopment” pursuant to N.J.S.A. 40A:12A, will incorporate the considerations listed below for Highlands Redevelopment Area designations in evaluating the applicable criteria under N.J.S.A. 40A:12A-5.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

1. Definitions.

- a. A “brownfield” site consists of a commercial or industrial site that is currently vacant or underutilized and on which there has been or is suspected to have been, a contaminant discharge.
- b. A “grayfield” site consists of a site supported by existing infrastructure that contains an industrial or commercial facility (not excluding one having a residential component) exhibiting signs of abandonment or underutilization, but without evidence or expectation of contamination.
- c. A “redevelopment project” or “redevelopment activity” refers to the re-use, reconstruction, or conversion to alternate use, of a brownfield site, a grayfield site, or a previously developed site that is currently vacant or underutilized in the Highlands Preservation Area. Redevelopment projects and activities may include but are not limited to: removal, reconstruction, or adaptive reuse of existing buildings and other structures; construction of new buildings and other structures; and conversion/restoration of a site or portions of a site for open space, recreation or conservation purposes of any kind.
- d. A “Highlands Redevelopment Area” consists of a property or group of properties designated as such by the Highlands Council, and which includes one or more of the following: a) a brownfield site; b) a grayfield site; and c) any previously developed site in the Highlands Preservation Area. A Highlands Redevelopment Area may include the intervening or surrounding lands which are significantly affected by or are necessary to support such sites, and will be subject to a Highlands Council-approved redevelopment plan setting forth the full scope and details of the proposed redevelopment project(s) and/or activities.

2. Redevelopment Projects and Activities.

- a. Redevelopment projects and activities that comply with all applicable land use ordinances (specifically including those developed for the Highlands Preservation Area) are encouraged in all Areas, Zones and Subzones of the Highlands Preservation Area. Such projects and activities are also subject to all applicable county, state, and federal regulatory requirements.
- b. Redevelopment projects and activities involving conversion to greenfields are particularly encouraged in environmentally constrained areas, where compliance with Highlands Preservation Area ordinance provisions for new development may not be feasible.
- c. In consideration of the foregoing, the Board will recommend specific sites, consisting of brownfields, grayfields, and/or other previously developed vacant or underutilized properties that should be considered for potential

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

redevelopment projects and/or activities in accordance with all applicable ordinances and regulatory requirements.

3. **Highlands Redevelopment Areas.** In assessing the potential for Highlands Redevelopment Area designations, the Planning Board incorporates the following relevant considerations:
 - a. Highlands Redevelopment Area designation in the Preservation Area is confined to: a) sites having 70% or greater impervious coverage, and/or b) sites designated as “Highlands brownfields” in accordance with NJDEP Preservation Area Rules (at N.J.A.C. 7:38-6.6). In addition to Highlands Council approval, a waiver is required from the NJDEP in conjunction with a Highlands Preservation Area Approval (HPAA).
 - b. Highlands Redevelopment Area designation will only be considered where lands are particularly suited to the proposed redevelopment plan, by virtue of a preponderance of existing characteristics such as, but not limited to: appropriate community location; availability of water and wastewater utility infrastructure and capacity; access to transit and/or other suitable transportation systems and networks; suitability for increased land use intensity or conversion to greenfields, as applicable; extensive coverage by impervious surfaces; proximity to community facilities and services; potential to embody and/or further smart growth principles; opportunity to protect resources; and potential to contribute to a sustainable local and/or regional economy.
 - c. Any redevelopment project or activity permitted under the auspices of Highlands Redevelopment Area redevelopment plan must be designed and developed in accordance with smart growth and Low Impact Development principles (see Section J).
 - d. Identification of opportunities for redevelopment projects and activities that are potentially suitable for Highlands Redevelopment Area designation in the Highlands Preservation Area should be assisted by the Highlands Council Redevelopment and Infill Analysis Tool. This review should also include any sites depicted in Exhibit C, “Highlands Contaminated Sites Inventory”. Information on Highlands Contaminated Site Inventories is available in the Highlands Council *Regional Land Use Conditions and Smart Design Guidelines Technical Report*.
 - e. In consideration of the foregoing, the Planning Board will identify potential Highlands Redevelopment Areas.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

HOUSING PLAN

The Planning Board adopted the municipality's Third Round Housing Element and Fair Share Plan, each prepared by the office of Burgis Associates, Inc., as amendments to the Township of Montville Master Plan, on May 27, 2010. These documents are maintained separately from this Highlands Element; however, it is important to note that all goals and objectives required for purposes of Plan Conformance as set forth by the Highlands Council have been incorporated into the Housing Element portion. The Borough submitted a petition to the Council on Affordable Housing seeking substantive certification of its Housing Element and Fair Share Plan on June 4, 2010.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

CONSERVATION PLAN

The basis for the Conservation Plan Element is the Township Highlands Environmental Resource Inventory (ERI), which is herewith adopted and incorporated in its entirety as an integral component of the Master Plan. The ERI was developed based on the vast store of resource information, technical data, and scientific analyses that provide foundation for the Highlands Regional Master Plan, including all Highlands Technical Reports and guidance documents. The ERI identifies, categorizes and delineates the wide array of natural resources and resource areas existing in the Township Highlands Preservation Area, and serves as a preeminent guidance document in Highlands Preservation Area community planning. In keeping with the general goals of the Highlands Element, it is the overarching policy of the Conservation Plan to safeguard the natural resources of the Township Highlands Preservation Area, ensuring sustainable use of renewable resources, protecting environmentally critical areas, and preserving significant natural areas. This policy directly advances the intents and purposes of the Highlands Act and is consistent with and furthers a number of the specific purposes of zoning as set forth under the MLUL (N.J.S.A 40:55D-2).

A. FOREST RESOURCES

Highlands Preservation Area Forest Resource delineations appear in the ERI maps duplicated herein at Exhibit D, “Forest Resource Area,” and Exhibit E, “Total Forest Area.”

This Plan seeks to balance the need to protect forest resources, biodiversity and water resources with the economic use and continued sustainable management of forests. It encourages active stewardship of forest resources in order to optimize the benefits and services forests provide such as clean air, clean water, soil protection, recreation area, wildlife habitat, and availability of forest products. The below-listed goals and objectives will guide the regulation and management of Township Highlands Preservation Area Forest Resources.

1. To protect and preserve extensive and, to the maximum extent possible, contiguous forests.
2. To limit development in the Forest Resource Area.
3. To prohibit clear-cutting except in accordance with a Forest Management Plan approved by the State Forester.
4. To require compliance with NJDEP Preservation Area Rules (N.J.A.C. 7:38) regarding forest protection in the case of all “major developments,” as defined therein.
5. To avoid deforestation, and where forest disturbance does occur, to require incorporation of Low Impact Development Best Management Practices (see Section K) and adherence to Forest Mitigation Plans.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

6. To ensure that site-specific forest resources are identified through project review and that those to remain are protected both during the construction of an approved development project and post-construction.
7. To maintain forest cover in the natural and built environment of the Township Highlands Preservation Area to the maximum extent possible.

B. HIGHLANDS OPEN WATERS AND RIPARIAN AREAS

Highlands Open Waters and Riparian Areas within the Highlands Preservation Area appear in ERI mappings duplicated herein at Exhibit G, “Highlands Open Waters” and Exhibit H, “Highlands Riparian Areas.” This Plan recognizes and incorporates the descriptions, definitions, delineations, and values regarding Highlands Open Waters and Riparian Areas as discussed in the ERI.

Highlands Open Waters are defined by the Highlands Act as all springs, streams including intermittent streams, wetlands, and bodies of surface water, whether natural or artificial (excluding swimming pools), located wholly or partially within the boundaries of the Highlands Region. The Highlands Act and the Highlands RMP establish the importance of providing protective buffers adjacent to Highlands Open Waters. Key functional values that such buffers provide or contribute to, include but are not limited to habitat, stormwater and flood water retention and filtration, water quality protection, temperature moderation, aquatic ecosystem integrity and channel integrity. Highlands Riparian Areas are the lands associated with and bordering Highlands Open Waters, but often extending beyond the Highlands Open Water buffers, that provide critical hydrologic, ecologic and pollutant attenuation functions for the Open Waters.

The below-listed goals and objectives will guide the regulation and management of Highlands Open Waters and Riparian Areas in the Township Highlands Preservation Area.

1. To protect, restore and enhance Highlands Open Waters and Riparian Areas.
2. To require protective buffers adjacent to Highlands Open Waters of sufficient width and composition to protect the integrity of the water resource from impairment due to proximate land uses and/or development activities. Minimum standards for such buffers should be consistent with those of the NJDEP and the RMP.
3. To seek opportunities to restore the functional value of Highlands Open Waters buffers where existing development or land uses have reduced or impaired their quality.
4. To seek opportunities to enhance Highlands Open Waters buffers by improving functional values while ensuring no net loss (see ERI assessment methodology).

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

5. To develop a Stream Corridor Protection and Restoration Management Plan that identifies: a) substantially impaired Highlands Open Waters buffer areas; b) opportunities for mitigation, restoration, and stabilization of such impaired buffer areas; and c) stream corridor areas that require buffers in excess of minimum standards and the characteristics necessary to provide optimum functional value.
6. With the exception of specific disturbances which may be authorized under a Highlands Council-approved Protection/Management Plan, to permit modifications to Highlands Open Waters, Highlands Open Water buffers, and Riparian Areas only for linear development where demonstrated that no feasible alternative exists to locate the linear development outside of such areas.
7. To limit disturbance of existing natural vegetation or increases in impervious area to the minimum feasible in areas beyond Highlands Open Waters buffer requirements; protect the water quality of adjacent Highlands Open Waters; and maintain or restore habitat value of the Riparian Area.

C. STEEP SLOPES

Steep slopes within the Highlands Preservation Area appear in the ERI mapping duplicated herein at Exhibit K, "Steep Slope Protection Areas." This Plan recognizes and incorporates the descriptions, definitions, delineations and values regarding steep slopes as discussed in the ERI.

The Township is particularly concerned with the potential negative impacts of land development practices that do not properly consider the constraints and challenges presented by steep slope areas. As discussed in the ERI, disturbance of such areas can trigger erosion and sedimentation, resulting in the loss of topsoil. Silting of wetlands, lakes, ponds and streams damages and degrades wetland and aquatic habitats, especially trout streams, which require rigorous water quality protections. Steep slope disturbance can also result in the loss of habitat quality, degradation of surface water quality, silting of wetlands, and alteration of drainage patterns. These processes, when severe, can result in land slumping and landslides that can damage both developed property and ecosystems. The severity and extent of slopes, soil characteristics, and land cover all affect the potential for damages from the disturbance of steep slopes.

Accordingly, the below-listed goals and objectives will guide the regulation and management of Township Highlands Preservation Area Steep Slope Protection Areas.

1. Maps and delineations of Steep Slope Protection Areas should be updated and improved as better information becomes available (i.e., through enhanced mapping anticipated to be made available from the Highlands Council) and/or as new areas are identified through project reviews pertaining to individual sites and properties.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

2. Land disturbance within all Steep Slope Protection Areas should incorporate Low Impact Development (see Section J) techniques to minimize the extent of such disturbance and the potential negative impacts resulting from it.
3. Land disturbance within areas of Severely and Moderately Constrained Slopes should be prohibited altogether, with exceptions only for linear development meeting the requirements of NJDEP Preservation Area Rules (at N.J.A.C. 7:38-3.8(c)1-4).

D. CRITICAL HABITAT

Critical Habitat within the Highlands Preservation Area appears in the ERI mappings duplicated herein at Exhibit L, “Critical Wildlife Habitat,” Exhibit M, “Significant Natural Areas,” and Exhibit N, “Vernal Pools.” This Plan recognizes and incorporates the descriptions, definitions, delineations and values regarding Critical Habitat as discussed in the ERI.

Biodiversity is the variety of plant species, animal species, and all other organisms found in a particular environment and is a critical indicator of ecological integrity. Habitat protection is critical to maintaining biodiversity including the many rare, threatened and endangered plant and animal species of the Highlands Region. There are three categories of Critical Habitat in the Highlands Region: 1) Critical Wildlife Habitat (habitat for rare, threatened or endangered animal species); 2) Significant Natural Areas (regionally significant ecological communities, including habitat for documented threatened and endangered plant species); and 3) vernal pools (confined, ephemeral wet depressions that support distinctive, and often endangered, species that are specially adapted to periodic extremes in water pool levels). Critical Wildlife Habitat and Significant Natural Areas are designated based on the presence of, and associated habitat required for, the survival and propagation of species of concern. Vernal pools shown in Exhibit N are those certified by the NJDEP. To protect the habitat requirements of vernal pool-breeding wildlife, the Highlands Council has determined that a terrestrial habitat buffer of 1,000 feet around vernal pools is required.

The below-listed goals and objectives will guide the regulation and management of Township Highlands Preservation Area Critical Habitat.

1. To prohibit the direct impact of new human development or expansion or increased intensity of existing development within Critical Habitat.
2. To promote the restoration and enhancement of impaired lands in Critical Habitat.
3. To develop and adopt a Habitat Conservation and Management Plan(s), including minimum performance standards and criteria as outlined below, for the protection, enhancement and restoration of lands within Critical Habitat.
 - a. Require use of Low Impact Development Best Management Practices (see Section J) to, in this order: 1) avoid the disturbance of Critical Habitat, 2)

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

minimize impacts to Critical Habitat, and 3) mitigate all adverse modification to Critical Habitat so that there is no net loss of habitat value. Habitat value is determined by quantity (e.g., acreage), quality (e.g., core forest vs. edge forest), type (e.g., scrub-shrub), and function (e.g., winter hibernacula for timber rattlesnakes). The mitigation requirement of no net loss of habitat value shall ensure that all four elements are accounted for and included in the mitigation design. Mitigation must meet the habitat and life-cycle requirements of the specific impacted species.

- b. Establish criteria for mitigation of disturbed Critical Habitat. Mitigation should be required for all adverse modification to Critical Habitat so that there is no net loss of habitat value.
 - c. Establish performance standards for the enhancement or restoration of historically disturbed Critical Habitat.
 - d. Provide a GIS or map-series Critical Habitat Overlay to identify Critical Habitat, that highlights:
 - i. Habitat in need of protection from fragmentation and other anthropogenic impacts;
 - ii. Habitat critical to maintaining wildlife and plant populations; and
 - iii. Habitat that serves other essential ecosystem functions, including, but not limited to, carbon sequestration and ground water recharge.
 - e. Develop guidelines for habitat stewardship, including, but not limited to prevention of habitat fragmentation through open space preservation and corporate, non-profit, and community involvement in creating, protecting, and restoring habitat.
4. To require that applications for development affecting Critical Habitat be subject to the standards and criteria outlined in the applicable Habitat Conservation and Management Plan.
- a. Prohibit direct impacts from new development or expansion or increased intensity of existing development that will jeopardize the continued existence of, or result in the likelihood of the destruction or adverse modification of Critical Habitat, except as permitted through the issuance of a waiver from the Highlands Council or the NJDEP.
 - b. Prohibit indirect impacts from activity that is off-site, adjacent to, or within Critical Habitat that will jeopardize the continued existence of, or result in the likelihood of the destruction or adverse modification of Critical Habitat, except as permitted through the issuance of a waiver from the Highlands Council or the NJDEP.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

- c. Prohibit modification of a vernal pools protection buffer, except as permitted through the issuance of a waiver from the Highlands Council or the NJDEP.
- d. Prohibit modifications to the delineation of Critical Wildlife Habitat and Significant Natural Areas, except as permitted through the issuance of a waiver from the Highlands Council or the NJDEP.

E. LAKE MANAGEMENT

Lake Management Areas within the Highlands Preservation Area appear in the ERI mapping duplicated herein at Exhibit O, "Lake Management Area." This Plan recognizes and incorporates the descriptions, definitions, delineations and issues of concern regarding lakes management as discussed in the ERI. Definitions include those pertinent to four lake management tiers: the Shoreland Protection Tier, the Water Quality Management Tier, the Scenic Resources Tier, and the Lake Watershed Tier.

Of particular concern to the Township are the potential negative impacts of land development practices that do not properly consider the constraints and challenges presented by lake management areas. As discussed in the ERI, overdeveloped, damaged and poorly managed shore land areas can degrade water quality, harm lake ecosystems, diminish natural aesthetic values, and cause an overall loss of property values for lake communities. Lakes can also be harmed by pollutant sources in the watershed area draining to them. Polluted lakes can, in turn, damage downstream streams and rivers.

Accordingly, the below-listed goals and objectives will guide the regulation and management of the Township Highlands Lake Management Area.

- 1. To prevent degradation of lake water quality, protect lake ecosystems, and promote lake area aesthetic values in the Lake Community Sub-Zone.
- 2. To protect lake water quality and associated ecosystems from the impacts of present and future development for all lakes. Applicable management strategies should address direct and proximate potential impacts from such activities as shoreline modification and development, dredging and pollutant discharges including those from septic systems, cesspools and other forms of wastewater management.
 - a. Ensure that land use and development activities in the Shoreland Protection Tier do not damage on-shore and near-shore ecological resources and cause direct pollutant loadings to lake waters.
 - b. Ensure that land use and development activities in the Water Quality Management Tier do not contribute continuous pollutant loadings to lake waters.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

- c. Develop and implement lake restoration management plans to protect, restore and, where possible, enhance lake water quality through management of pollutant sources in the Lake Watershed Tier.
3. For each lake in the municipality identified as water quality-impaired, to either ensure compliance with Total Maximum Daily Load (TMDL) limitations adopted by the NJDEP, or to develop and implement lake restoration management plans. Such plans should include at minimum, watershed delineation, description of point and nonpoint sources of pollution in the watershed, lake monitoring schedules, existing and proposed in-lake management techniques, and recommended watershed best management practices.
4. To protect the character of the Township Highlands Lake Management Area.
 - a. Assess existing zoning requirements to determine whether amendments are necessary to ensure that development is compatible with shoreline uses and activities and that it occurs at a scale and intensity appropriate to the Lake Management Area.
 - b. Protect the visual and scenic resources in the Scenic Resources Tier through such means as vegetative screening, limits on tree removal, shore line building/disturbance setbacks, and building height limitations.
5. To maximize opportunities for public access to lakes and lake areas (excluding those under private ownership/management) for appropriate passive and active recreational uses that do not degrade lake environments.
6. To maintain lakes or restore lake beds and downstream areas when lakes are drained. Damages to lake bed and/or downstream stream habitat, for example, should be prevented, mitigated or restored as needed following the breach or removal of a dam. Achieving this goal will require dedicated sources of funding from public and private sources, as applicable.

F. WATER RESOURCES AVAILABILITY

Highlands Preservation Area water availability is represented by the ERI mapping duplicated herein at Exhibit P, "Net Water Availability." This Plan recognizes and incorporates the descriptions, definitions, analyses and issues of concern regarding water availability as discussed in the ERI. Based on the Low Flow Margin analytical method described in the ERI, the Township lies within 1 HUC14 subwatershed having positive net water availability, and 5 HUC14's determined to be in deficit.

The availability of water for human use is a critical factor in determining the capacity for growth and continued economic vitality in the Township Highlands Preservation Area. The availability of water for ecological purposes is critical to sustaining the aquatic ecosystems

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

of streams, ponds and lakes. Of particular concern to the Township is the potential for overuse of water to reduce base flows, impair ecological function and integrity, and reduce the reliability of potable water supplies that the municipality depends upon.

Accordingly, the below-listed goals and objectives will guide the regulation and management of Township Highlands Preservation Area water availability.

1. To protect, restore (if applicable) and enhance the availability of surface and ground water in the Township Highlands Preservation Area.
2. To ensure that increasing water demands do not exceed Net Water Availability or exacerbate existing deficits of subwatersheds.
3. To strictly limit consumptive and depletive water uses to the water availability in each HUC14 subwatershed.
4. To provide limited water availability (Conditional Water Availability) within a Current Deficit Area with appropriate standards regarding its use and rigorous requirements for mitigation, effective until such time as a municipal Water Use and Conservation Management Plan has been developed and adopted.
5. Within Protection Zone subwatersheds, to give highest priority for the use of non-agricultural Net Water Availability or Conditional Water Availability addressing a documented existing or imminent threat to public health and safety from contaminated domestic and other on-site water supplies that is of sufficient scale to justify a public water supply and where no alternative is feasible that would sufficiently assure long-term protection of public health and safety. To assign secondary priority to the following:
 - a. A designated Highlands Redevelopment Area; and
 - b. Any project proposing affordable housing in excess of the obligation otherwise generated by it.
6. Within Existing Community Zone subwatersheds, to give highest priority for use of Net Water Availability or Conditional Water Availability to addressing a documented threat to public health and safety from contaminated water supplies. To assign secondary priority to the following:
 - a. Designated TDR Receiving Zones;
 - b. Infill development;
 - c. Designated Highlands Redevelopment Areas;
 - d. Projects proposing affordable housing in excess of the obligation otherwise generated by them; and

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

- e. New areas for development that meet all other requirements.
7. To require the use of water conservation, recycling and reuse methods (where appropriate) and devices for any redevelopment or development activity, including renovations to existing buildings, to minimize consumptive water use. This should include mandatory collection and use of stormwater to serve non-agricultural irrigation needs and to the extent feasible, other non-potable purposes.
8. To ensure that proposed public water supply and wastewater service areas, and new or increased water allocations and transfers will not directly or indirectly cause or contribute to a Net Water Availability deficit, and where feasible will help mitigate any existing deficit.
9. To ensure efficient and effective use of water availability, reduction and elimination of water deficits, and mitigation of new consumptive or depletive use in any Current Deficit Areas or subwatersheds that could become deficit areas based on projected development and water uses.
10. To permit new consumptive or depletive water uses within a Current Deficit Area only under the auspices of a Water Use and Conservation Management Plan; or until such a Plan is in place, to permit such uses only within the allocated Conditional Water Availability and provided that mitigation of the proposed use is accomplished within the same HUC14 subwatershed through: a permanent reduction of existing consumptive and depletive water uses; ground water recharge in excess of the requirements of N.J.A.C. 7:8 (Stormwater Management Rules); or other permanent means.
11. To develop and implement a Water Use and Conservation Management Plan that sets forth the manner and mechanisms by which to achieve each of the preceding goals and objectives.
 - a. Where developed for Current Deficit Areas, the Plan must include provisions to reduce or manage consumptive and depletive uses of ground and surface waters as necessary to reduce or eliminate deficits in Net Water Availability, or to ensure continued stream flows to downstream Current Deficit Areas from Existing Constrained Areas, to the maximum extent practicable within each HUC14 subwatershed.
 - b. For Current Deficit Areas, the Plan must in addition include a detailed implementation plan and schedule indicating how and when the current deficit will be resolved in the applicable subwatershed(s) prior to approval of new water uses in the subwatersheds with the most severe deficits (e.g., in excess of 0.25 million gallons per day), and the plan shall be implemented prior to initiation of new water uses.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

- c. The Plan must also ensure that transfers between or from Highlands Subwatersheds occur only where no viable alternative exists to meet public health, safety and welfare needs and where no impairment of subwatershed resources will result.

G. PRIME GROUND WATER RECHARGE AREAS

Prime Ground Water Recharge Areas within the Highlands Preservation Area appear in the ERI mapping duplicated herein at Exhibit Q, "Prime Ground Water Recharge Areas." This Plan recognizes and incorporates the descriptions, definitions and delineations for Prime Ground Water Recharge Areas (PGWRAs) as discussed in the ERI. Prime Ground Water Recharge Areas are those lands within a HUC14 subwatershed that most efficiently provide in the aggregate, 40 percent of total drought recharge volume for the HUC14 subwatershed, as determined in accordance with parameters set forth in the ERI. Protection of such areas is clearly vital to maintaining the quality and quantity of the ground water resources upon which both human and non-human communities in the Highlands Preservation Area so heavily rely.

Accordingly, the below-listed goals and objectives will guide the regulation and management of Township Highlands Prime Ground Water Recharge Areas.

1. To protect, enhance, and restore the quantity and quality of Prime Ground Water Recharge Areas.
2. To require use of Low Impact Development (see Section J) and other Best Management Practices to maximize natural ground water recharge and minimize the need for engineered recharge methods.
3. To restrict land use and development activities that reduce natural ground water recharge volumes in PGWRAs or that may contribute to or result in degradation of ground water quality, whether directly or indirectly.
4. To avoid disturbance of lands identified as PGWRAs to the maximum extent feasible, and to minimize such disturbance where it cannot be avoided. Where disturbances do occur in PGWRAs, to require mitigation measures to enhance pre-construction recharge volumes.
5. To prohibit land uses and activities that pose significant risk of ground water contamination from locations delineated as PGWRAs.
6. To require that Major Potential Contaminant Sources (PCS) (as listed at Appendix A) in locations delineated as PGWRA, incorporate ongoing management of toxic chemical sources and prohibition of non-permitted discharges, so that the potential for ground water contamination is minimized and the opportunity for discharge discovery and control is maximized.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

7. To identify and implement opportunities for the restoration or enhancement of recharge in Prime Ground Water Recharge Areas and other lands through such means as the retrofit or rehabilitation of stormwater recharge facilities, land management improvements and reforestation.
8. To achieve a net improvement in ground water volume and quality through enhanced infiltration, pretreatment and other available means.

H. WATER QUALITY

This Plan incorporates the descriptions, definitions and summary data regarding water quality by HUC14, as discussed in the ERI. In addition, it incorporates as Exhibit R, "HUC 14s on NJDEP Impaired Waters List," as duplicated from the ERI. Water quality affects drinking water, recreation, ecosystems and aesthetic beauty. The most common parameters that may impair surface and ground water quality are fecal coliform bacteria, phosphorus, temperature, arsenic and nitrate-nitrogen. These and other contaminants can either cause health risks if ingested or harm native biota, resulting in non-attainment of designated water uses for the water body.

Water quality is influenced by the type and intensity of land use adjacent to and upstream of the water body. Pollutants are contributed to the environment from a wide variety of nonpoint sources (NPS) including human development (through stormwater and residential runoff, septic systems, fertilizer applications on lawns, and Brownfields or contaminated sites), domestic or captive animals, agricultural practices (crop farming, livestock, and manure applications), and wildlife (large populations). Pollutants from these sources can reach water bodies directly, through overland runoff, or through stormwater conveyance facilities. Point sources also exist, primarily wastewater treatment plants serving communities or industrial facilities.

Accordingly, the below-listed goals and objectives apply to the management and regulation of water quality in the Township Highlands Preservation Area.

1. To protect, restore (if applicable) and enhance water quality in the Highlands Preservation Area.
2. To remedy the pollutant sources associated with existing or historic land uses in conjunction with redevelopment opportunities.
3. To ensure that land use and development is permitted only in such locations, at such densities, and in such manner as to ensure sustainable use of Highlands Preservation Area water resources and continued protection and management of critical lands for water quality purposes.
4. To ensure that the municipal portion of any Areawide Water Quality Management Plan or Wastewater Management Plan will not directly or indirectly support

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

development that would be in violation of any adopted Total Maximum Daily Load (TMDL) limits established by NJDEP.

5. To adopt and implement stormwater management controls through a municipal Stormwater Management Plan.
6. To require use of applicable Low Impact Development (see Section J) and Best Management Practices to protect the quality of ground and surface waters.

I. WELLHEAD PROTECTION

Wellhead Protection Areas within the Highlands Preservation Area appear in the ERI mapping duplicated herein at Exhibit S, "Wellhead Protection Areas." This Plan recognizes and incorporates the descriptions, definitions and delineations for Wellhead Protection Areas (WHPAs) as discussed in the ERI. Highlands Preservation Area WHPAs are delineated for community water supply wells based upon time of travel, reflecting the time required for ground water to flow into the well. WHPAs are composed of three tiers based upon a 2-year (Tier 1), 5-year (Tier 2), and 12-year (Tier 3) time of travel. Each tier includes the area of each smaller tier within it.

Protection of ground water resources that directly provide water to potable water supply wells is vital to the public health, safety, and welfare of the community. It is also of primary importance to ensure continued availability of clean drinking water to all that rely upon it. Through regulation of land use, physical facilities and other activities within WHPAs, the potential for ground water contamination can be reduced by preventing the introduction and migration of pollutants into ground water sources that supply water supply wells.

Accordingly, the below-listed goals and objectives will guide the regulation and management of Township Highlands Wellhead Protection Areas.

1. To identify and ensure proper management of existing land uses within Wellhead Protection Areas that have a significant potential for contributing pollutants of concern to ground water.
2. To protect and enhance ground water and water supply resources within Wellhead Protection Areas consistent with the source water assessments for each water supply source.
3. To prohibit land uses and activities that pose significant risk of ground water contamination from locations delineated as Tier 1 and Tier 2 Wellhead Protection Areas, with enhanced protections within the first 200 feet of any public water system wellhead.
4. To require that Major Potential Contaminant Sources (PCS) (as listed at Appendix A) in locations delineated as Tier 1 Wellhead Protection Areas, incorporate ongoing management of toxic chemical sources and prohibition of non-permitted discharges,

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

so that the potential for ground water contamination is minimized and the opportunity for discharge discovery and control is maximized.

5. To ensure that stormwater management plans pertinent to both development applications and municipal-wide planning, address wellhead protection requirements.
6. To encourage stormwater reuse for non-agricultural irrigation and other non-potable water purposes to minimize the volume of stormwater discharges (other than from clean sources) within a Tier 1 or Tier 2 Wellhead Protection Area.
7. To restrict development activities that pose threats to the water quality of public water supply wells.
8. To ensure that development activities and existing land use activities implement best management practices to protect the quality of ground water within Wellhead Protection Areas.
9. To ensure that the uses, structures or activities permitted within utility service areas, as proposed within the municipal portion of the Areawide Water Quality Management Plan or Wastewater Management Plan, will not adversely affect any Wellhead Protection Area.

J. LOW IMPACT DEVELOPMENT

This Plan embraces the concept of Low Impact Development (LID) and seeks to ensure its maximum use in land development activities throughout the Highlands Preservation Area. LID encompasses a broad array of development and management techniques that can minimize or mitigate the potential adverse impacts of land use and development on the natural environment. LID is used in stormwater management, resource management, “green” building, and sustainable site design. In stormwater management for example, LID techniques can be employed to capture rainfall, filter it through existing vegetation, and maximize its absorption by on-site soils in order to recharge ground water supplies. In site design, LID would incorporate strategies to reduce site disturbance, limit impervious coverage, and integrate existing natural features affecting the site and/or its immediate surroundings into the proposed layout and design.

To accomplish such aims, specific LID standards should be developed and incorporated into Township land use regulations. Because LID practices and innovations continue to emerge, these should include, but by no means be limited to the following:

1. Stormwater management LID standards that preserve or mimic the natural hydrologic features and characteristics of the land.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

- a. Use of stormwater management features that maintain, restore and enhance the pre-existing natural drainage patterns of the site.
 - b. Limitations on impervious coverage allowances to maximize stormwater infiltration and reduce runoff.
 - c. Requirements for site-specific hydrologic studies which identify the velocity, volume and pattern of water flow into, through and flowing from a parcel proposed for development.
 - d. Requirements that stormwater management systems employ a “design with nature” approach by use of grass channels, dry swales, wet swales (vegetated channels designed to retain water or marshy conditions that support wetland vegetation), infiltration basins, bio-swales and water gardens, constructed wetlands, green roofs, and other low impact approaches to attenuate and control stormwater and provide multiple environmental benefits.
2. LID practices that minimize land disturbance during construction activities.
- a. Requirements for site-specific analysis of environmental features and constraints as an integral component of site design.
 - b. Limitations on site disturbance, soil compaction, clearing and grading to the minimum necessary to allow for permissible development.
 - c. Provisions to minimize soil erosion and airborne dust during construction and to protect streams and other water bodies from silt and sedimentation.
3. LID best management practices where any development application proposes disturbance of a Highlands resource, including but not limited to Steep Slope Protection Areas, Forest Areas, Critical Habitat Areas, Highlands Open Waters and Riparian Areas, and Prime Ground Water Recharge Areas.
- a. Highlands resources should be identified as a first step in site planning.
 - b. To the maximum extent practicable Highlands resources should be avoided or their disturbance minimized through site design.
 - c. The quality and value of Highlands resources located on development sites should be maintained by use of LID strategies that minimize the impacts of development to the maximum extent possible.
4. LID practices in design of sites, buildings, structures and roadways. Development and redevelopment projects should follow a prescribed conservation design planning process that considers existing site features and site context; maximizes opportunities for open space and connections to open space systems; and

TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT

incorporates LID practices in all aspects of stormwater management, site layout, and resource protection. In addition to the previously listed items (1-3, above) these include but are not limited to the following:

- a. Use of water conservation measures in site layout and structures, including but not limited to such practices as water efficient landscaping (including use of native and drought-tolerant plant species), rain collection systems, use of gray water, and water-efficient landscape irrigation.
- b. Use of low maintenance landscaping that encourages retention and planting of native vegetation and minimizes lawn areas and use of fertilizers and pesticides.
- c. Use of pervious paving materials and minimization of impervious surfaces.
- d. Use of micro-climate conditions to maximize solar gain for winter heating and minimize solar gain during high temperature summer conditions.
- e. Re-use and recycling of building materials when development involves demolition.
- f. Inclusion of energy-efficient features in site layouts and buildings.
- g. Roadway design standards (subject to RSIS limitations) that incorporate LID techniques to address stormwater management, limit impervious coverage, ensure planting of native and drought-resistant vegetation, and integrate other “green street” design initiatives.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

UTILITY SERVICES PLAN

It is the overarching policy of this Plan to ensure that development of the Highlands Preservation Area does not exceed the available environmental and infrastructural capacity to support it. The Utilities Services Plan recognizes and incorporates the following Exhibits, as described and discussed in the ERI and duplicated herein: Public Community Water Systems (Exhibit T); and Highlands Domestic Sewerage Facilities (Exhibit U).

This Plan recognizes that future development must only occur within the carrying capacity of water resources, as to both quality and quantity. It also recognizes the importance of ensuring that water supply and wastewater utility capacities are made available in ways that provide maximum benefit within the constraints of water availability and water quality protection, and are used in ways that provide cost-effective and efficient service. Utility services support more dense development than on-site wells and septic systems, and therefore can provide for more housing and job creation per square mile. They also can result in more intensive environmental impacts, however, and a greater strain on available water resources. It is of particular concern to the Township, that utility service locations occur in the most appropriate portions of the Highlands Preservation Area and that development reliant upon wells and/or septic systems occur only at densities that can be sustained by existing environmental characteristics.

Accordingly, the below-listed goals and objectives will guide Township regulation and management of water and wastewater utilities, and use and maintenance of septic systems.

- A. To prohibit the expansion or creation of public water supply systems, wastewater collection and treatment systems and community on-site treatment facilities in the Preservation Area unless approved through a Highlands Applicability Determination (HAD) or an HPAA with waiver pursuant to the NJDEP Preservation Area rules at N.J.A.C. 7:38.
- B. To identify those lands of the Preservation Area that may be appropriate for the extension or creation of public water supply systems, wastewater collection and treatment systems and community on-site treatment facilities for redevelopment that would meet the waiver requirements of the NJDEP Preservation Area rules at N.J.A.C. 7:38 regarding public health and safety or redevelopment.
- C. To ensure that on-site wastewater system discharges do not exceed the natural capacity of ground water to attenuate loadings, exacerbate existing nitrate impairment, or contribute to potential nitrate impairment for subwatersheds of the Highlands Preservation Area.
- D. To ensure that all development in areas not served by public water supply or wastewater collection and treatment systems is at a density that can be supported by on-site wells and subsurface septic systems, respectively. With respect to septic systems, to determine such densities on the basis of NJDEP Preservation Area Rules.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

- E. To ensure the development of a Township Highlands Preservation Area septic system management/maintenance plan.
- F. To develop a Wastewater Management Plan for the Township, including the Highlands Preservation Area.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

CIRCULATION PLAN

The existing Master Plan has a Circulation Plan Element providing detailed information on existing and proposed transportation infrastructure within, or providing access to and from the municipality, including information on all modes and supporting facilities and services. This Plan supplements the existing Element, as applicable to the Highlands Preservation Area, to include the additional information and goals and objectives listed below.

The “Highlands Roadway Network” (Exhibit V) and “Highlands Transit Network” (Exhibit W) maps together illustrate the regional transportation network and facilities of the Township Highlands Preservation Area. Municipal roadways and transportation features interface with those of the region and the State as a whole, as discussed and illustrated in the underlying Circulation Plan Element for the municipality.

The Planning Board currently anticipates, proposes and/or has identified need for modifications to the portion of the transportation system located within the Highlands Preservation Area, as listed and briefly described below:

1. Parking improvements;
2. Bicycle lanes or bike trail installations;
3. Pedestrian safety enhancements;
4. Sidewalk/lighting improvements;
5. Provision of multi-modal linkages to/between community facilities;
6. Roadway infrastructure improvements.

As discussed in the ERI, future and existing development and redevelopment in the Highlands Preservation Area relies upon a complex network of roads, railways and bridges serving not only the municipality, but the county, the region and the state as a whole. A variety of modes of transportation are vital to ensuring efficient movement of people and goods, including but not limited to automobile, bus, rail, truck, bicycle and pedestrian. By promoting smart growth principles and efficient land use, the municipality and the Highlands Region as a whole can expand access to a multi-modal transportation system while protecting environmentally sensitive areas and Highlands resources.

Accordingly, the following goals and objectives shall guide the development, improvement, and on-going management of the transportation network and supporting facilities of the Township Highlands Preservation Area.

1. To ensure that transportation facilities and infrastructure are designed and located in a manner that achieves optimal efficiencies in land use and provision of service, while at the same time, protecting the environmental resources and critical environmental areas of the Highlands Preservation Area.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

2. To enhance opportunities for pedestrian and bicycle access, mobility and safety, through provision of sidewalks, walking trails, pedestrian crosswalks, bicycle lanes and trails, bicycle racks, and networked linkages that both access and connect community facilities, parks, schools and shopping areas.
3. To improve public safety through implementation of traffic calming measures in areas with high pedestrian activity.
4. To provide for safe and efficient pedestrian connections including features such as sidewalks, proper lighting, signage, shelters and “green street” initiatives such as those of the New Jersey Department of Transportation’s (NJDOT) Pedestrian Safety Initiative.
5. To enhance roadway corridors and encourage pedestrian activity, where appropriate, by installation of ample sidewalk areas with aesthetic enhancements such as street trees, decorative lighting, and benches.
6. To promote safe routes for children to travel to and from school, potentially with the financial and technical assistance of NJDOT’s Safe Routes to School Program.
7. To optimize use of existing roadway capacity by appropriate means, such as increased bus, van, jitney and car pool ridership.
8. To identify roadways designated as scenic byways and, to the extent of municipal jurisdiction, to protect and preserve their defining characteristics in conjunction with the scenic viewsheds they provide access to.
9. To recognize and support the unique needs of the agricultural industry to move farm vehicles and goods along transportation corridors, and to establish safe travel routes for farmers and agri-tourism, as appropriate in the Highlands Preservation Area, to ensure the safety and viability of farming as an occupation.
10. To evaluate the potential growth-inducing effects of roadway improvements that will increase traffic capacity, such as substantial new land use, new residents or new employment.
11. To prohibit road improvements in areas for which a Growth-Inducing Study demonstrates that proposed improvements do not support the resource protection and smart growth policies otherwise established by the Highlands Element, or that are likely to be growth-inducing for lands with limited or no capacity to support human development without adverse impact on Highlands Preservation Area resources.
12. To limit road improvements where roads are constrained by topography, adjacent forested lands, or other sensitive environmental features such as critical habitat.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

13. To ensure that road improvements are designed to enhance community character and to avoid adverse impacts to adjoining or otherwise affected properties.
14. To promote land use patterns that support a balance of jobs to housing as a means of reducing motor vehicle trips and average trip lengths.
15. To seek and encourage to the extent applicable, development and redevelopment in areas proximate to rail stations and along bus routes.
16. To promote development of mixed land uses, where appropriate, in locations that result in reduced motor vehicular trips and average trip lengths.
17. To permit and encourage use of shared parking areas, driveways, and other such infrastructure to limit paved surfaces and maximize efficiencies.
18. To ensure coordination between transportation planning and the Land Use Plan Element and to integrate smart growth principles into both.

TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT

LAND PRESERVATION AND LAND STEWARDSHIP PLAN

The existing Master Plan has an Open Space and Recreation Plan Element providing detailed information on existing and proposed open space preservation and recreational opportunities in the community. This Plan supplements the existing Element, as applicable to the Highlands Preservation Area, to include the additional information and goals and objectives listed below.

A mapped inventory of Preserved Lands in the Township Highlands Preservation Area, current through August 2012, appears at Exhibit X, "Preserved Lands" (duplicated from the ERI). This Plan in addition incorporates (from the ERI) Exhibit Y, "Highlands Conservation Priority Areas," Exhibit Z, "Highlands Special Environmental Zone," Exhibit AA, "Preserved Farms, SADC Easements, All Agricultural Uses," and Exhibit BB, "Important Farmland Soils." This Plan recognizes and incorporates the definitions, derivations and delineations used to develop these maps, as provided in the ERI.

The municipality contains 2,803 total acres of Highlands Preserved Lands, as depicted in Exhibit X. This includes preserved open space under ownership by the Federal government, the State, the County, the Township, as well as the Town of Boonton. In addition, the exhibit shows preserved farmland and water supply watershed lands, which are used for the purpose of water supply but are not deed restricted nor permanently protected from future development. In the Township Highlands Preservation Area, there are 1,526 acres of Highlands Preserved Lands, including 1,022 acres of County-owned land, 472 acres of Township-owned land, and 32 acres of water-supply watershed land.

Highlands Conservation Priority Area lands are those designated a high priority for preservation due to exceptional water and ecological resource value. The priority order derives from the Highlands Council Resource Assessment methodology, which identifies and ranks Highlands lands based on a combination of indicators, including but not limited to: watershed conditions, Highlands Open Waters, riparian areas, prime ground water recharge areas, forests, critical habitat and steep slopes.

Lands within the Highlands Special Environmental Zone are those having the highest priority ranking for preservation based on the Highlands Council Resource Assessment and for which development is expressly prohibited. Preservation of these lands is vital to: a) protecting Highlands Preservation Area water resources and environmentally sensitive lands; b) protecting water supply reservoirs and other critical water features; c) creating large contiguous areas of environmentally sensitive lands; d) creating habitat corridors; and e) connecting existing preserved open space.

All Agricultural Uses includes lands currently serving farming and/or other agricultural purposes, whether permanently deed restricted or not. The map of *Important Farmland Soils* provides a delineation of the four farmland soil classifications as prepared by the U.S.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

Department of Agriculture (USDA), NRCS, Soil Survey Geographic Database for farmland soil quality, including:

- a) Prime Farmland Soils - Soils having the best combination of physical and chemical characteristics for producing food, feed, forage, fiber and oilseed crops. It has the soil quality, growing season, and moisture supply needed to produce high yields of crops when treated and managed according to acceptable farming methods. Prime farmland soils are not excessively erodible or saturated with water for a long period of time, and they either do not flood frequently or are protected from flooding.
- b) Soils of Statewide Importance – Soils that produce high yields of crops when treated and managed according to acceptable farming methods. This soil may support yields as high as Prime farmland if conditions are favorable.
- c) Unique Farmland Soils - Soils used for special crops (such as cranberries in the New Jersey Pinelands). Unique soils are determined on a statewide basis by the State Soil Conservation Committee.
- d) Locally Important Farmland Soils - Soils designated and ranked by the County Agriculture Development Board (CADB). Farmland of Locally Important soils include those soils that are not Prime or of Statewide Importance and are used for the production of high value food, fiber, or horticultural crops.

The following goals and objectives will guide the future identification, prioritization, dedication, and stewardship of Preserved Lands in the Township Highlands Preservation Area:

1. To apply Highlands Council prioritization criteria in making determinations regarding non-agricultural Land Preservation (whether by fee simple or easement dedication), which are ordered as follows:
 - a. Lands within the Highlands Special Environmental Zone;
 - b. Lands within Highlands Conservation Priority Areas; and
 - c. Lands within Highlands Resource Areas generally, including but not limited to forested portions of Forest Resource Areas, Critical Habitat Areas, and Riparian Areas, particularly any portion of a Resource Area designated as “High Integrity” or “High Resource Value.”
2. To maintain a current Recreation and Open Space Inventory (ROSI) where required by the NJDEP Green Acres Program.
3. To seek ways to establish and fund local land acquisition for preservation and stewardship programs or to expand existing open space and stewardship programs.

TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT

4. To identify lands subject to stewardship programs within this Land Preservation and Land Stewardship Plan and to provide that information to the Highlands Council.
5. To require that conservation or land stewardship easements imposed during the course of development applications be enforceable by the Highlands Council and at least one of the following entities, as qualified and amenable in accordance with the particular circumstances: the Township, the CADB, the SADC, Green Acres, or a non-profit land trust organized pursuant to § 501 (c)(3) of the federal tax code and engaged in the protection of land for the purpose of providing long-term stewardship of land resources.
6. To establish a stewardship and monitoring program for preserved lands owned by or dedicated to the Township. This objective may be accomplished with the assistance of a non-profit land trust organized pursuant to § 501 (c)(3) of the federal tax code and engaged in the protection of land for the purpose of providing long-term stewardship of land resources.
7. To develop and implement a Forest Management Plan or Forest Stewardship Plan consistent with the standards of the NJ Forest Stewardship Program for application to municipally-owned forest lands.
8. To ensure periodic monitoring of easement restrictions protecting Critical Habitat Areas, associated species and ecological communities from any changes in land use or management practices that would impair these resources.
9. To implement Riparian Area restoration practices on Preserved Lands that give priority to ecological and watershed protection measures.
10. To identify and preserve opportunities for outdoor recreation, including a variety of active and passive recreation options, in such locations and in such manner as to ensure environmental resource protections, while addressing the needs of the local population for physical activity, social interaction, connection with nature and the natural environment, and enjoyment of the outdoors.
11. To promote the Right to Farm Act and to incorporate land use regulations that are consistent with and further its intents and purposes.
12. To promote the long-term viability of the local agricultural industry by promoting and utilizing existing county, State, and federal agriculture related programs and developing land use regulations and programs where appropriate, in support of direct marketing, organic farming, niche markets, agri-tourism initiatives such as farmers' markets and roadside stands (located on or off the site of an active farm), ancillary business opportunities, community supported agriculture, and other such projects, programs, or activities.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

COMMUNITY FACILITIES PLAN

The existing Master Plan has a Community Facilities Plan Element providing detailed information on all existing community facilities, including but not limited to government offices, fire, police, and rescue squad facilities, parks and playgrounds, educational facilities, libraries, public works facilities and yards, treatment works, storage depots, and so forth. This Plan supplements the existing Element, as applicable to the Highlands Preservation Area, to include the additional goals and objectives listed below.

The overriding policy of this Plan is to ensure that community facilities reflect community needs while minimizing resource impacts and maximizing the efficiency of resource use. Achieving this aim requires attention to the design and location of community facilities. Accordingly, the below-listed goals and objectives will guide community facilities in the Township Highlands Preservation Area.

1. To locate and maintain community facilities and services that support compact development patterns and shared services, and provide a high level of service.
2. To identify existing and planned community facilities and to encourage shared service opportunities, whether at intra- or inter-municipal levels.
3. To identify for all such facilities, realistic options to enhance energy efficiencies, incorporate “green” building materials and technologies, reduce pollutant emissions, and minimize “carbon footprints;” and to develop a community strategy for implementing them.
4. To consider and incorporate all feasible Low Impact Development techniques in the design, development, operation and management of existing and proposed community facilities. (For description and discussion of LID techniques, see Conservation Plan Element.)
5. To incorporate the goals, objectives and resource protections discussed throughout this Highlands Element into the planning and development of properties and facilities under municipal jurisdiction.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

SUSTAINABLE ECONOMIC DEVELOPMENT PLAN

A sustainable economy is important to the well-being of the Township and the wider economic region of which it is a part. It is the intent of the Planning Board to examine this issue and to prepare an economic development plan for future adoption, which will set forth strategies for strengthening the local economy and/or the municipal contribution toward the wider economy to which it belongs.

The goals and objectives of the Sustainable Economic Development Plan in addition include, but are not limited to:

1. To develop appropriate strategies to improve the local tax base and create jobs and economic opportunities, while remaining consistent with the other policies and objectives of the Highlands Element.
2. To ensure opportunities for home office, entrepreneurial and other small business activities, as appropriate.
3. To identify appropriate opportunities for development and/or redevelopment, including possible brownfield redevelopment that may further the goal of economic sustainability.
4. To encourage development of small business incubator programs, particularly those focused on advancing specific goals and objectives of the Highlands Element, such as initiatives in compact design, native species landscaping, Low Impact Development, energy efficiency and resource conservation.
5. To coordinate with the Highlands Council and other applicable State and/or county agencies to develop or participate in eco-, agri-, and/or heritage tourism programs, as appropriate.

HISTORIC PRESERVATION PLAN

The existing Master Plan has an Historic Preservation Plan Element setting forth the applicable goals and objectives, criteria for historic designation, and specific properties of historic interest in the community. This Plan supplements the existing Element, as applicable to the Highlands Preservation Area, to include the additional information and goals and objectives listed below.

A. HISTORIC, CULTURAL, AND ARCHAEOLOGICAL RESOURCES

The Township survey of historic sites appears as a map within the ERI, which is duplicated herein at Exhibit CC, "Historic, Cultural, and Archaeological Resource Inventory." The specific list of affected properties and a brief discussion pertaining to each is provided below. The list comes directly from the State Historic Preservation Office (SHPO) (as of August 2012), which includes: 1) all properties listed on the State or National Register of Historic Places; 2) all properties which have been deemed eligible for listing on the State or National Register; and 3) all properties for which a formal SHPO opinion has been issued.

This Plan recognizes that the historic, cultural and archaeological resources of the Highlands Preservation Area form an essential component of its character and aesthetic quality. They preserve a part of the history of the Township Highlands Preservation Area and provide a link to its past. They remind us of significant people, places and events in our history and they provide vital information about what life was like in this community in earlier times.

Accordingly, the below-listed goals and objectives shall apply to the Historic, Cultural, and Archaeological resources in the Highlands Area.

1. To examine the character and qualities of the community's Historic, Cultural, and Archaeological resources to gain further understanding of the extent of their contributions to the aesthetics, character, economic vitality, and sense of place of the community.
2. To consider the educational value of the community's Historic, Cultural, and Archaeological resources and encourage opportunities to celebrate and share information about the community's heritage.
3. To consider the character and qualities of the community's Historic, Cultural, and Archaeological resources in any development application that may affect them, whether directly or indirectly.
4. To examine the potential for development and adoption of regulatory provisions that are protective of the Historic, Cultural, and Archaeological resources of the community.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

5. To consider the character and qualities of the community's Historic, Cultural, and Archaeological resources in development of the Land Use Plan, Community Facilities Plan, Circulation Plan, and all other aspects of the Highlands Element.

The sites, districts and properties listed below are included in the Highlands Historic, Cultural, and Archaeological Resources Inventory within the Preservation Area.

Pennsylvania-New Jersey Interconnection Bushkill to Roseland Transmission Line

1. (SHPO ID#5117)
2. Vreeland House (SHPO ID#5046)

Additionally, the following archaeological sites are included in the Highlands Historic, Cultural, and Archaeological Resources Inventory. (It is noted that because the locations of archaeological sites are kept confidential to prevent looting, this list may include archaeological sites in both the Preservation Area as well as Planning Area. However, this document and all applicable provisions apply solely to the Township Preservation Area.)

1. Cook / Stephens House Site (SHPO ID#3593)
2. Iron Mines (SHPO ID#3595)
3. John I. Jacobus House Site (SHPO ID #___)
4. Prehistoric Site (28-Mr-195) (SHPO ID#3584)
5. Prehistoric Site (28-Mr-197) (SHPO ID#2161)
6. Schneider Prehistoric Archaeological Site (SHPO ID#2136)
7. Van Duyne-Como Prehistoric Archaeological Site (SHPO ID#2166)
8. Van Ness Prehistoric Archaeological Site (SHPO ID#2167)

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

B. SCENIC RESOURCES

The Township baseline survey of scenic resources appears at Exhibit DD, “Baseline Scenic Resources Inventory,” duplicated from the ERI. The specific list of affected properties and a brief discussion pertaining to each is provided below. The list comes directly from the Highlands Council as a first-step inventory of Scenic Resources having potential for local and/or regional designation. It includes national historic landmarks and federal, State and county publicly-owned parks, forests, and recreation areas.

The Highlands Council also adopted a Procedure for Nomination, Evaluation and Inventory of Highlands Regionally Significant Scenic Resources which establishes the process for formal nomination and inclusion of additional scenic resources in the Highlands Scenic Resource Inventory. The process requires the adoption and implementation of management plans to ensure that the scenic resources are protected and maintained.

This Plan recognizes the value and importance of scenic resources in preserving the aesthetic qualities of the Township Highlands Preservation Area. Accordingly, the below-listed goals and objectives shall apply to the future management of Scenic Resources in the Highlands Preservation Area.

1. To ensure that human development does not adversely affect the character or value of resources which are listed on the Highlands Scenic Resources Inventory.
2. To require that the impact of proposed human development on the scenic resources of the Highlands Preservation Area be addressed during local development review.
3. To utilize Highlands Scenic Resource designation standards, as applied at the local level, in considering scenic resources for designation.
4. To require that all development applications include identification of any scenic resources in the Highlands Region that are listed on the Highlands Scenic Resources Inventory and may be affected by the proposed development.
5. To develop regulatory standards to protect Scenic Resources from negative impacts due to development.
6. To develop minimum standards for the protection and enhancement of the Scenic Resources listed in the Highlands Scenic Resources Inventory.

The following locations are listed in the Highlands Scenic Resources Inventory within the Preservation Area:

- a) Pyramid Mountain Natural Historic Area
- b) Pyramid Mountain Addition

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

RELATIONSHIP OF MASTER PLAN TO STATE/REGIONAL/LOCAL PLANS

By adoption of this Highlands Element, the Township Master Plan is brought into alignment with the Highlands Regional Master Plan (RMP). The Highlands Element incorporates all of the policies, goals, and objectives of the Highlands RMP that are relevant to the use and development of land in the Township Highlands Preservation Area. The Highlands Element calls for the development and adoption of various land use regulations and specific environmental management plans, which together will effectuate its vision and in so doing, advance the intents and purposes of the Highlands RMP.

The Highlands Act provides that any portion of a municipality located in the Highlands Preservation Area is exempt from the State Planning Commission (SPC) Plan Endorsement process. It provides further that once the RMP has attained Plan Endorsement from the SPC for the Planning Area, Highlands Council approval of Plan Conformance with respect to lands in the Planning Area shall be deemed the equivalent of Plan Endorsement.

By aligning the municipal Master Plan with the Highlands RMP, its consistency with the State Development and Redevelopment Plan (SDRP) is achieved. A map depicting the municipality's SDRP Planning Areas appears at Exhibit EE. The Highlands Element furthers SDRP policies, goals, and objectives in many ways, not least of which are the following:

1. Seeking to protect, preserve, restore, and enhance the natural resources of the Highlands Preservation Area;
2. Encouraging the use of smart growth principles in locations of the Area deemed appropriate for development and/or redevelopment;
3. Protecting historic, cultural and aesthetic resources;
4. Encouraging a sustainable local economy;
5. Protecting agricultural resources, supporting local agricultural businesses, and promoting sustainable agricultural practices;
6. Preserving open space and providing for an array of active and passive recreational opportunities; and
7. Ensuring a viable and well-integrated transportation network that incorporates and encourages multi-modal options and efficiency of land use.

The Highlands Element modifies the relationship of the Township development plan to those of the county and contiguous municipalities insofar as it affects the intents for land use and development within the Township Highlands Preservation Area. Given that the Highlands Element introduces a substantial number of new constraints to development based on environmental resources and carrying capacities, it is anticipated that the future impacts from development of the Highlands Preservation Area will be reduced from previous trends. A complete understanding will not exist however, until further analysis is

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

undertaken to determine the full impacts of conformance with the RMP on the municipal Land Use Plan. An important component of that analysis will be in regard to watershed-based planning. To the extent that the Township shares a HUC14 subwatershed with other municipal and/or county entities, a cooperative planning effort involving all parties will be vital to ensuring sound use and management of the available water resources. It will also be important to understand which, if any, of the adjoining municipalities and/or the county conform to the Highlands RMP and for what portions of their land areas. The land uses, the permitted densities and intensities of development, and the locations and extent of anticipated growth in neighboring Highlands communities that are also pursuing conformance with the RMP are all subject to change. Until information is available concerning such decision-making, a comparison between these master plans will not be meaningful. Further discussion of these aspects will therefore be provided in the next amendment to the Master Plan.

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

ACRONYMS

| | |
|-------|--|
| CADB | County Agriculture Development Board |
| ERI | Environmental Resource Inventory |
| EDU | Equivalent Dwelling Unit |
| FAR | Floor Area Ratio |
| GIS | Geographic Information Systems |
| HAD | Highlands Applicability Determination |
| HDC | Highlands Development Credit |
| HPAA | Highlands Preservation Area Approval |
| HUC | Hydrologic Unit Code |
| LID | Low Impact Development |
| MLUL | Municipal Land Use Law (of the State of New Jersey) |
| NJDA | New Jersey Department of Agriculture |
| NJAC | New Jersey Administrative Code |
| NJDEP | New Jersey Department of Environmental Protection |
| NJDOT | New Jersey Department of Transportation |
| NJSA | New Jersey Statutes Annotated |
| NPS | Nonpoint Source |
| NRCS | Natural Resources Conservation Service |
| PCS | Potential Contaminant Source |
| PGWRA | Prime Ground Water Recharge Area |
| RMP | Regional Master Plan (of the New Jersey Highlands Water Protection and Planning Council) |
| ROSI | Recreation and Open Space Inventory |
| SADC | State Agriculture Development Committee |
| SCD | Soil Conservation District |
| SDRP | State Development and Redevelopment Plan |
| SHPO | State Historic Preservation Office |
| SPC | State Planning Commission |
| TDR | Transfer of Development Rights |
| TMDL | Total Maximum Daily Load |
| TSP | Technical Service Provider |
| USDA | United States Department of Agriculture |
| WHPA | Wellhead Protection Area |

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

EXHIBITS

- A.** Township Highlands Preservation Area
- B.** Township Land Use Inventory
- C.** Highlands Contaminated Sites Inventory
- D.** Forest Resource Area
- E.** Total Forest Area
- F.** *[Reserved]*
- G.** Highlands Open Waters
- H.** Highlands Riparian Areas
- I.** *[Reserved]*
- J.** *[Reserved]*
- K.** Steep Slope Protection Areas
- L.** Critical Wildlife Habitat
- M.** Significant Natural Areas
- N.** Vernal Pools
- O.** Lake Management Area
- P.** Net Water Availability
- Q.** Prime Ground Water Recharge Areas
- R.** HUC 14s on NJDEP Impaired Waters List
- S.** Wellhead Protection Areas
- T.** Public Community Water Systems
- U.** Highlands Domestic Sewerage Facilities
- V.** Highlands Roadway Network
- W.** Highlands Transit Network
- X.** Preserved Lands
- Y.** Highlands Conservation Priority Areas
- Z.** Highlands Special Environmental Zone
- AA.** Preserved Farms, SADC Easements, All Agricultural Uses
- BB.** Important Farmland Soils
- CC.** Historic, Cultural, and Archaeological Resource Inventory
- DD.** Baseline Scenic Resources Inventory
- EE.** SDRP Planning Areas

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

APPENDIX A MAJOR POTENTIAL CONTAMINANT SOURCES

Land uses and activities determined by the Highlands Council (based on New Jersey Safe Drinking Water Act regulations and NJDEP regulations) to be Major Potential Contaminant Sources include the following:

1. Underground fuel and chemical storage and oil tanks regulated by NJDEP under provisions of the Underground Storage of Hazardous Substances Act (N.J.S.A. 58:10A-21 et seq.).
2. Above-ground storage facility for a hazardous substance or waste with a cumulative capacity greater than 2,000 gallons.
3. Automotive service center (repair & maintenance).
4. Dry cleaning processing facility.
5. Road salt storage facility.
6. Cemetery.
7. Highway maintenance yard.
8. Truck, bus, locomotive maintenance yard.
9. Site for storage and maintenance of heavy construction equipment and materials.
10. Site for storage and maintenance of equipment and materials for landscaping, excluding household storage and maintenance of such equipment.
11. Livestock operation containing 300 or more Animal Units (AU) [1 AU= 1000 pounds of live animal weight] as defined by the NJ Department of Agriculture in its Criteria and Standards for Animal Waste Management, at NJAC 2:91.
12. Quarrying and/or mining facility.
13. Asphalt and/or concrete manufacturing facility.
14. Junkyard/auto recycling and scrap metal facility.
15. Residential or agricultural motor fuel in NJDEP exempted underground storage tanks (i.e., under 1,000 gallons).

**TOWNSHIP OF MONTVILLE
HIGHLANDS PRESERVATION AREA MASTER PLAN ELEMENT**

APPENDIX B MINOR POTENTIAL CONTAMINANT SOURCES

Land uses and activities determined by the Highlands Council (based on New Jersey Safe Drinking Water Act regulations and NJDEP regulations) to be Minor Potential Contaminant Sources include the following:

1. Underground storage of hazardous substance or waste of less than 50 gallons.
2. Underground heating oil storage tank with a capacity of less than 2,000 gallons.
3. Sewage treatment facility regulated by a NJPDES permit granted under NJAC 7:14A.
4. Industrial waste line.
5. Septic system disposal field.
6. Facility requiring a ground water discharge permit issued by the NJDEP pursuant to N.J.A.C 7:14A et seq.
7. Stormwater retention-recharge basin on an industrial property receiving runoff from surfaces other than roof areas.
8. Dry well on an industrial property receiving runoff from surfaces other than roof areas.
9. Waste oil collection, storage and recycling facility.
10. Agricultural chemical bulk storage and mixing or loading facility including crop dusting facilities.
11. Above-ground storage of hazardous substance or waste in quantities of less than 2,000 gallons.
12. Livestock operation containing 8 or more Animal Units (AU) [1 AU= 1000 pounds of live animal weight] or those receiving 142 or more tons of animal waste per year as defined by the NJ Department of Agriculture pursuant to its Criteria and Standards for Animal Waste Management, at NJAC 2:91.



Exhibit A: Highlands Preservation Area Master Plan Element



Regional Master Plan Overlay Zone Designation

- | | |
|--|-----------------------------|
| Zone | |
| Protection | Lakes Greater Than 10 acres |
| Conservation | Preservation Area |
| Existing Community | Municipal Boundaries |
| Sub-Zone | |
| Existing Community Environmentally Constrained | |
| Conservation Environmentally Constrained | |
| Lake Community | |
| Wildlife Management | |

Montville Township



1 inch = 0.943 miles



SEPTEMBER 2011

Exhibit B. Township Land Use Inventory







Exhibit C: Highlands Contaminated Site Inventory



Highlands Contaminated Site Inventory

- Tier 1 Sites
- Tier 1 Sites (Polygons)
- Tier 2 Sites
- Preservation Area
- Municipal Boundaries

Montville Township




1 inch = 0.943 miles





SEPTEMBER 2011

Exhibit D: Forest Resource Area



-  Forest Resource Area
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles





SEPTEMBER 2011

Exhibit E: Total Forest Area



-  Forested Areas
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles



SEPTEMBER 2011



Exhibit F: Forest Subwatersheds



Forest Integrity by HUC14 Subwatershed

-  *Low*
-  *Moderate*
-  *High*
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles





SEPTEMBER 2011

Exhibit G: Highlands Open Waters



-  Highlands Open Water Buffers (300ft)
-  Streams
-  Wetlands
-  Lakes & Ponds
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles





SEPTEMBER 2011

Exhibit H: Highlands Riparian Areas



-  Riparian Area
-  Preservation Area
-  Municipal Boundaries

Montville Township



1 inch = 0.943 miles



SEPTEMBER 2011



Exhibit I: Watershed Values



Watershed Values by HUC14 Subwatershed

- Low
- Moderate
- High
- Preservation Area
- Municipal Boundaries

Montville Township




1 inch = 0.943 miles



SEPTEMBER 2011



Exhibit J: Riparian Integrity



Riparian Integrity by HUC14 Subwatershed

-  Low
-  Moderate
-  High
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles



SEPTEMBER 2011



Exhibit K: Steep Slope Protection Areas



Steep Slopes

-  Moderate
-  Severe
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles





SEPTEMBER 2011

Exhibit L: Critical Wildlife Habitat



- Critical Wildlife Habitat
- Preservation Area
- Municipal Boundaries

Montville Township




1 inch = 0.943 miles





SEPTEMBER 2011

Exhibit M: Significant Natural Areas



-  Significant Natural Areas
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles





SEPTEMBER 2011

Exhibit N: Vernal Pools



-  Vernal Pools + 1000ft Buffer
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles





SEPTEMBER 2011

Exhibit O: Lake Management Area



-  Lakes & Ponds
-  Lake Management Area
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles



SEPTEMBER 2011

Exhibit P: Net Water Availability





Net Water Availability By HUC14
 Million Gallons Per Day (MGD)

- 0.10 - 0.39
- 0.05 - 0.09
- 0.00 - 0.04
- 0.09 - 0.00
- 0.99 - -0.10
- 7.10 - -1.00

- Preservation Area
- Municipal Boundaries

Montville Township




1 inch = 0.943 miles





SEPTEMBER 2011

Exhibit Q: Prime Ground Water Recharge Areas



- Prime Groundwater Recharge Areas
- Preservation Area
- Municipal Boundaries

Montville Township




1 inch = 0.943 miles



SEPTEMBER 2011



Exhibit R: HUC 14s on NJDEP Impaired Waters List



Impaired Waters Overall Assessment by HUC14 Subwatershed

- Non Impacted
- Insufficient Data Available
- Moderate
- Water Quality Impaired
- Preservation Area
- Municipal Boundaries

Montville Township




1 inch = 0.943 miles



SEPTEMBER 2011

Exhibit S: Wellhead Protection Areas





- Public Community Wells
- Public Non-Community Wells

Wellhead Protection Areas

- 2-Year Tier
- 5-Year Tier
- 12-Year Tier

- Preservation Area
- Municipal Boundaries

Montville Township




1 inch = 0.942 miles





SEPTEMBER 2011

Exhibit T: Public Community Water Systems



-  Public Community Water Systems
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles



SEPTEMBER 2011



Exhibit U: Highlands Domestic Sewerage Facilities



Highlands Domestic Sewerage Facilities

-  Existing Area Served
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles



SEPTEMBER 2011

Exhibit V: Highlands Roadway Network



Roadway Network

 Interstate Highways

 U.S. Routes

 State Routes



 County Routes

 Local Routes

 Preservation Area

 Municipal Boundaries

Montville Township




1 inch = 0.943 miles




SEPTEMBER 2011

Exhibit W: Highlands Transit Network



- | | |
|--------------------------------|----------------------|
| Rail Network | Rail Stations |
| Boonton Line | Park and Ride Sites |
| Main Line & Bergen County Line | Private Bus Lines |
| Morris and Essex Line | NJ Transit Bus Lines |
| Raritan Valley Line | Airports |
| Freight Rail Lines | |
| Freight Rail Lines | |
| Abandoned Freight Rail | |

Montville Township




1 inch = 0.943 miles





SEPTEMBER 2011

Exhibit X: Preserved Lands



- | | |
|---|-------------------------------|
| Preserved Lands | Conservation Easements |
| Federal Open Space | Green Acres |
| State Open Space | SADC Easements |
| County Open Space | SADC Final |
| Municipal Open Space | SADC Preserved |
| Non-Profit/Private Open Space | Municipal Boundaries |
| Water Supply Watershed Lands | Preservation Area |
| Preserved Farmland | |
| Highlands Transfer of Development Lands | |

Montville Township




1 inch = 0.943 miles



SEPTEMBER 2011



Exhibit Y: Highlands Conservation Priority Areas



Conservation Priority Area

-  Moderate
-  High
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles





SEPTEMBER 2011

Exhibit Z: Highlands Special Environmental Zone



-  Special Environmental Zone
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles



SEPTEMBER 2011



Exhibit AA: Preserved Farms, SADC Easements, All Agricultural Uses



SADC Easements

-  SADC Final
-  SADC Preserved
-  Preserved Farmland
-  Agriculture Uses
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles



SEPTEMBER 2011



Exhibit BB: Important Farmland Soils



Important Farmland Soils

-  Prime Farmland
-  Farmland of Local Importance
-  Farmland of Statewide Importance
-  Farmland of Unique Importance
-  Preservation Area
-  Municipal Boundaries

Montville Township




1 inch = 0.943 miles





SEPTEMBER 2011

Exhibit CC: Historic, Cultural, and Archaeological Resources Inventory



-  Preservation Area
-  Municipal Boundaries
-  Archaeological Grids (1 sqmi)
-  NJ Historic Districts
-  Historic Property Points
-  Historic Property Polygons

Montville Township




1 inch = 0.942 miles





SEPTEMBER 2011

Exhibit DD: Baseline Scenic Resources Inventory



- Scenic Resources
- Municipal Boundaries
- Preservation Area

Montville Township




1 inch = 0.943 miles



SEPTEMBER 2011

Exhibit EE. SDRP Planning Areas



- Municipal Boundaries
- Parcels
- Highlands Preservation Area

splan2_Montville

State Planning Areas

- METROPOLITAN
- FRINGE
- ENVIRONMENTALLY SENSITIVE
- PARKS & NATURAL AREAS

| | | | | | | | |
|---|--|--|---------|-----------|---------|-------------|-----|
| Dwg. Title | Exhibit FF - SDRP Planning Areas | Project No. | 2192.02 | Dwg. Date | 7/22/09 | Drawn By | RW |
| BURGIS ASSOCIATES, INC. PROFESSIONAL PLANNERS / LANDSCAPE ARCHITECTS 25 WESTWOOD AVENUE WESTWOOD, N.J. 07675 201-666-1811 FAX: 201-666-2599 | Project Title Highlands Master Plan Element TOWNSHIP OF MONTVILLE MORRIS COUNTY, NEW JERSEY | Dwg. Scale | N.T.S. | Sheet No. | 1 of 1 | Drawing No. | SPA |
| | | 2009 COPYRIGHT BA NOT TO BE REPRODUCED | | | | | |